



TOP SECTION: 7,870#
1' RISER SECTION: 2,010#
2' RISER SECTION: 3,720#
BOTTOM SECTION: 7,190#
TOTAL WEIGHT: 20,790#
SEPTIC TANK 3000 GALLON INDIANA
DATE: 4-11-17
DWG #ST-IN-3000

**S & M
PRECAST, INC.**

"NPCA" CERTIFIED PLANT

16700 SIMA GRAY RD, HENRYVILLE, IN 47126
Phone: (812) 246-6258 Fax: (812) 294-4862

SPECIFICATIONS
CONCRETE: 4500 PSI @ 28 DAYS
REINFORCEMENT: ASTM A-615, GR 60
LOAD DESIGN: NON-TRAFFIC 18" MAX COVER